

Practical Checklist for On-Site Use

Pre-Works Planning:

- Identify soil types, slope, rainfall patterns, and sensitive areas.
- Flag areas prone to erosion or dust generation.
- Plan stabilisation, hard-engineering, and sediment control measures.
- Include responsibilities in inductions and toolbox talks.

On-Site Controls:

- Check erosion and sediment controls are correctly installed.
- Maintain and monitor stockpiles to prevent dust and runoff.
- Reduce the area open to erosion
- Check for sediment tracking on roads, cleaning as needed.
- Do daily inspections and check controls before rainfall events.

Team Engagement:

- Toolbox talks on erosion, sediment, and dust risks.
- Encourage crew to report potential risks early.
- Reinforce the importance of proactive controls as part of site culture.